

**TESTING FOR THE VERIFICATION OF COMPLIANCE OF
PV INVERTER WITH:
TECHNICAL PRESCRIPTION C10/11 OF SYNERGRID.
EDITION 2.1 (01.09.2019)
(REQUIREMENTS FOR TYPE A GENERATING PLANT)**

Procedure: PE.T-LE-62

Test Report Number: **2221 / 0055-2**
 Type.....: **AC Coupled Storage Converter**
 Tested Model: **ME 3000SP**
 Variant Models: **N/A**

APPLICANT

Name: Shenzhen SOFARSOLAR Co., Ltd.
 Address.....: 401, Building 4, AnTongDa Industrial Park, District 68,
 XingDong Community, XinAn Street, BaoAn District, Shenzhen
 City, Guangdong Province, P.R. China

TESTING LABORATORY

Name: SGS Tecnos, S.A. (Electrical Testing Laboratory)
 Address.....: C/ Trespaderne, 29 - Edificio Barajas 1
 28042 Madrid (Spain)

Conducted (tested) by: Roger Hu
 (Project Engineer)



Reviewed and Approved by: Jacobo Tevar
 (Technical Reviewer)



Date of issue: 25/02/2021

Number of pages: 82

Important Note:


- This document is issued by the Company under its General Conditions of service accessible at http://www.sgs.com/terms_and_conditions.htm. Attention is drawn to the limitation of liability, indemnification and jurisdiction issues defined therein. Any holder of this document is advised that information contained hereon reflects the Company's findings at the time of its intervention only and within the limits of Client's instructions, if any. The Company's sole responsibility is to its Client and this document does not exonerate parties to a transaction from exercising all their rights and obligations under the transaction documents.
- This document cannot be reproduced except in full, without prior written approval of the Company. Any unauthorized alteration, forgery or falsification of the content or appearance of this document is unlawful and offenders may be prosecuted to the fullest extent of the law.
- Unless otherwise stated the results shown in this test report refer only to the sample(s) tested as received. **Information of derived or extension models of the range as provided by the applicant, (if any), is included in this report only for informative purposes.** The Company SGS shall not be liable for any incorrect results arising from unclear, erroneous, incomplete, misleading or false information provided by Client.

Test Report Historical Revision:

Test Report Version	Date	Resume
2221/0055-2	25/02/2021	First issuance

INDEX

1	SCOPE.....	4
2	GENERAL INFORMATION	5
2.1	Testing Period and Climatic conditions	5
2.2	Equipment under Testing	5
2.3	Factory information	7
2.4	Reference Values	7
2.5	Test equipment list.....	8
2.6	Measurement uncertainty.....	9
2.7	Test set up.....	10
2.8	Definitions.....	12
3	RESUME OF TEST RESULTS	13
4	TEST RESULTS.....	14
4.1	Automatic separation system	14
4.2	Power Quality.	15
4.2.1	Rapid voltage changes.....	15
4.2.2	Flickers	18
4.2.3	Harmonic	21
4.2.4	Unbalances.....	31
4.3	Integrated automatic separation system	32
4.3.1	Overvoltage 10 min mean Test.....	33
4.3.2	Overvoltage Test.....	34
4.3.3	Undervoltage Test.....	35
4.3.4	Overfrequency Test.....	36
4.3.5	Underfrequency Test.....	37
4.3.6	LoM Test.....	38
4.4	Operating ranges	41
4.4.1	Operating frequency range and Maximum admissible power reduction in case of underfrequency	41
4.4.2	Continuous operating voltage range	44
4.5	Immunity to disturbance	45
4.5.1	RoCoF immunity	45
4.5.2	Voltage ride through (UVRT/OVRT)	48
4.6	Active response to frequency deviations.....	48
4.6.1	Power response to overfrequency	48
4.6.2	Power response to underfrequency	52
4.7	Power response to voltage changes.....	56
4.7.1	Q(P) Capabilities.....	56
4.7.2	Q(U) capabilities	63
4.7.3	Cos φ setpoint.....	65
4.7.4	Cos φ (P) capabilities.....	67
4.7.5	Specific for a small power-generating plant	69
4.7.6	Specific for another (not small) power-generating plant	71
4.7.7	Voltage related active power reduction P(U).....	71
4.7.8	Provision of additional fast reactive current during faults and voltage steps.....	73
4.8	Connection and starting to generate electrical power.....	74
4.8.1	Automatic reconnection after tripping	74
4.8.2	Starting to generate electrical power	75
4.9	Ceasing and reduction of active power on set point	78
4.9.1	Ceasing active power	78
4.9.2	Active power reduction following setpoint	78
4.10	Communication – Remote monitoring and control.....	79
5	PICTURES	80
6	ELECTRICAL SCHEMES.....	82

	Report N. 2221/0055-2	Page 4 of 82
C10/11: 2019		

1 SCOPE

SGS Tecnos, S.A. (Electrical Testing Laboratory) has been contract by **Shenzhen SOFARSOLAR Co., Ltd.**, in order to perform testing according to Technical Prescription C10/11 of Synergrid. Edition 2.1 (01.09.2019). Specific technical prescriptions regarding power-generating plants operating in parallel to the distribution network.

EUT comply with requirements for **type A** generating plant connect to LV grid define in the standard as following:

The power limits considered for application in the scope of this regulation are the following:

- Type A: $0.8\text{kw} \leq P_{\text{MAX Capacity}} < 1\text{MW}$
- Type B: $1\text{MW} \leq P_{\text{MAX Capacity}} < 25\text{MW}$

2 GENERAL INFORMATION

2.1 TESTING PERIOD AND CLIMATIC CONDITIONS


The necessary testing has been performed on 20th November 2020 and 18th February 2021

All the tests and checks have been performed at 25 ± 5°C, 96 kPa ± 10 kPa and 40% RH ± 10% RH).

SITE TEST

Name: Shenzhen SOFARSOLAR Co., Ltd.
 Address.....: 401, Building 4, AnTongDa Industrial Park, District 68, XingDong Community, XinAn Street, BaoAn District, Shenzhen City, Guangdong Province, P.R. China

2.2 EQUIPMENT UNDER TESTING


Apparatus type: AC Coupled Storage Converter
 Installation.....: Fixed installation
 Manufacturer.....: Shenzhen SOFARSOLAR Co., Ltd.
 Trade mark.....: 
 Model / Type reference.....: ME 3000SP
 Serial Number: ZE1ES050M31999
 Software Version.....: V2.80
 Checksum: N/A
 Rated Characteristics: Battery side: 42-58Vdc, Max. Charging/Discharging Current: 60A, Max. Charging/Discharging Power: 3000VA, AC side: 230Vac, 13A, 3000VA, 50Hz

Date of manufacturing: 2020

Test item particulars

Input.....: DC
 Output.....: L/N/PE
 Class of protection against electric shock...: Class I
 Degree of protection against moisture.....: IP 65
 Type of connection to the main supply: Signal phase – Fixed installation
 Cooling group.....: Heat sink
 Modular: No
 Internal Transformer.....: No

Copy of marking plate:

**Note:**

1. The above markings are the minimum requirements required by the safety standard. For the final production samples, the additional markings which do not give rise to misunderstanding may be added.
2. Label is attached on the side surface of enclosure and visible after installation
3. Labels of other models are as the same with ME 3000SP's except the parameters of rating.

Equipment under testing:

- **ME 3000SP**

The results obtained apply only to the particular sample tested that is the subject of the present test report. The most unfavorable result values of the verifications and tests performed are contained herein. Throughout this report a comma (point) is used as the decimal separator.

2.3 Factory information

Factory Name: **Dongguan SOFAR SOLAR Co., Ltd.**
 Factory Address: 1F - 6F, Building E, No. 1 JinQi Road, Bihu Industrial Park, Wulian Village, Fenggang Town, Dongguan City, Guangdong Province, P.R. China.

2.4 REFERENCE VALUES

The values presented in the following table have been used for calculation of referenced values (p.u.; %) though the report.

Reference Values	
Design active power, P_D in kW	2.7
Rated apparent power, S_n in kVA	3
Rated wind speed (only WT), v_n in m/s	N/A
Rated current (determined), I_n in A	13.0
Rated output voltage, (phase to phase) U_n in Vac	230
Note: In this report p.u. values are calculated as follows: -For Active & Reactive Power p.u values are reference to S_n -For Currents p.u values, the reference is always I_n -For Voltages p.u values, the reference is always U_n	

2.5 TEST EQUIPMENT LIST

From 2020/11/20 to 2021/01/05:

From	No.	Equipment Name	Model No.	Equipment No.	Calibration Date	Equipment calibration due date
Sofar Solar	1	Voltage probe	SanHua / SI-9110	152627	2020/01/14	2021/01/13
	2	Voltage probe	SanHua / SI-9110	111134	2020/01/14	2021/01/13
	3	Power analyzer	ZLG / PA3000	PA3004-P0004-1422	2020/01/14	2021/01/13
	4	Current probe	CYBERTEK / CP1000A	C181000922	2020/01/14	2021/01/13
	5	Current probe	CYBERTEK / CP1000A	C181000925	2020/01/14	2021/01/13
	6	Temperature & Humidity meter	Anymeters / TH101B	ZB-WSDJ-001	2020/01/14	2021/01/13
	7	Oscilloscope	Agilent / DS05014A	MY50070266	2020/01/14	2021/01/13
SGS	8	True RMS Multimeter	Fluke / 289C	22930028 (GZE012-53)	2020/02/21	2021/02/20

From 2021/01/06 to 2021/02/18:

From	No.	Equipment Name	Model No.	Equipment No.	Calibration Date	Equipment calibration due date
Sofar Solar	1	Voltage probe	SanHua / SI-9110	111539	2021/01/05	2022/01/04
	2	Voltage probe	SanHua / SI-9110	111134	2021/01/05	2022/01/04
	3	Power analyzer	ZLG / PA3000	C8202005651809220002	2021/01/05	2022/01/04
	4	Current probe	CYBERTEK / CP1000A	C181000922	2021/01/05	2022/01/04
	5	Current probe	CYBERTEK / CP1000A	C181000929	2021/01/05	2022/01/04
	6	Temperature & Humidity meter	Anymeters / HTC-1	WSDJ-007	2020/12/28	2021/12/28
	7	Oscilloscope	Keysight / DS0X3014T	MY59243036	2021/01/05	2022/01/04
SGS	8	True RMS Multimeter	Fluke / 289C	22930028 (GZE012-53)	2020/02/21	2021/02/20

2.6 MEASUREMENT UNCERTAINTY

Associated uncertainties through measurements showed in this this report are the maximum allowable uncertainties.


Magnitude	Uncertainty
Voltage measurement	±1.5 %
Current measurement	±2.0 %
Frequency measurement	±0.2 %
Time measurement	±0.2 %
Power measurement	±2.5 %
Phase Angle	±1°
Temperature	±3° C

Note1: Measurements uncertainties showed in this table are maximum allowable uncertainties. The measurement uncertainties associated with other parameters measured during the tests are in the laboratory at disposal of the petitioner.

Note2: Where the standard requires lower uncertainties that those in this table. Most restrictive uncertainty has been considered.

2.7 TEST SET UP

Below is the simplified construction of the test set up.



Test Conditions		
Condition	Value	Comments
Point of measurement	EUT Output (Low Voltage)	Equipment enounced in section 2.4 of this report has been used in the point of measurement
Short circuit ratio at the measurement point (S_k / S_n)	$S_k / S_n = 60\text{kVA} / 3\text{kVA} = 20$	
If the PGU is connected directly to the medium-voltage grid and a step-up transformer is installed between the PGU and the grid (which is not part of the PGU), a standard transformer must be used, the rated apparent power of which corresponds at least to the rated apparent power of the PGU being evaluated.	Connect to LV grid only	
MV Tansformer: Short circuit Power	--	Not applicable measured in Low voltage side
MV Tansformer: Network impedance Phase Angle	--	Not applicable measured in Low voltage side
MV Tansformer: Service voltage U_c	--	Not applicable measured in Low voltage side
LV Isolation transformer: Nominal Power (kVA)	--	Transformerless
LV Isolation transformer: Short circuit voltage U_k (%)	--	Transformerless
LV Isolation transformer: Tap position	--	Transformerless

Test Conditions		
Condition	Value	Comments
MV Side: Additional impedance	--	Not applicable measured in Low voltage side
LV Side: Additional impedance	Active 0 Ω Reactive 0 Ω	
The THDSU of the voltage which includes all integer harmonics up to the 50th order must be smaller than 5%. It is measured as the 10-minute mean at the PGU terminals while the PGU is not generating any power.	See section 2.5.2 of this report	
The voltage, measured as a 10-minute mean at the PGU terminals, must lie within a range of ±10% of the rated voltage	Phase A: 0.11% Phase B: 0.07% Phase C: 0.14%	
The voltage unbalance, measured as a 10-minute mean at the PGU terminals, must be less than 2%.	-0.335%	
The grid frequency, measured as a 0.2 second mean, must lie within a range of ±1% of the rated frequency around the rated frequency. The rate of change of the grid frequency, measured as a 0.2 second mean, must be smaller than 0.2% of the rated frequency per 0.2 seconds.	Tested Max. Value 50.008Hz Tested Min. Value 49.993Hz Tested Avg. Value:50.002Hz	
Note 1: These test conditions have been used in all the test performed in Sections 4 of this report. Note 2: See also the test bench information table in this section		

Different equipments have been used to take measures as it shows in chapter 2.3. Current and voltage clamps have been connected to the inverter input / output for all the tests.

All the tests described in the following pages have used this specified test setup.

The test bench used includes:

EQUIPMENT	MARK / MODEL	RATED CHARACTERISTICS	OWNER / ID. CODE
AC source	Keysight / N8957APV	60kVA max. 45-65Hz	Sofar Solar / DE17202422
PV source	Chroma / 61860	60kVA max.	Sofar Solar / 6186038000446

2.8 DEFINITIONS

EUT	Equipment Under Testing	Hz	Hertz
A	Ampere	V	Volt
Un	Nominal Voltage	p.u	Per unit
In	Nominal Current	Pn	Rated Active Power
Ia	Active Current	Qn	Rated Reactive Power
Ir	Reactive Current	Sn	Rated Apparent Power
MV	Medium Voltage	THC	Total Harmonic Current
LV	Low Voltage	TDD	Total Demand Distortion
HV	High Voltage	I _h	Harmonic Current
UVRT	Under-Voltage Ride Through	Plt	Severity of Flicker Long-Term
OVRT	Over-Voltage Ride Through	ms	Millisecond
Pst	Severity of Flicker Short-Term	s	Second
dc	Maximum Variation of Voltage	min	Minute
d max	Maximum Absolute Value of Voltage Variation	P	Active Power
		Q	Reactive Power
fn	Nominal frequency	PF	Power Factor
IGBT	Insulated-Gate Bipolar Transistor	Nr.	Number
RMS	Root Mean Square	POC	Point of Connection
S _{k, fic}	Short-circuit apparent power	Meas.	Measured
AC	Alternating Current	Des.	Desired
DC	Direct Current	PGU	Power Generating Unit
DSO	Distribution System Operator	P _D	Design active power
EESS	Electrical energy storage system	P _M	Momentary active power
EES	Electrical energy storage	Smax	Maximum apparent power
Pmax	Maximum active power		
P _A	Available active power		

3 RESUME OF TEST RESULTS

INTERPRETATION KEYS

Test object does meet the requirement : **P** Pass
 Test object does not meet the requirement : **F** Fails
 Test case does not apply to the test object : **N/A** Not applicable
 To make a reference to a table or an annex..... : See additional sheet
 To indicate that the test has not been realized : **N/R** Not realized

REPORT SECTION	C10/11: 2019 SECTION	CHAPTER OF THE STANDARD	RESULT
4.1	4.1.7 (2)	Automatic Separation System	--
4.2	8.2	Power quality	--
4.2.1	8.2.2	Rapid voltage changes	P
4.2.2	8.2.3	Flickers	P
4.2.3	8.2.4	Harmonic	P
4.2.4	8.2.5	Unbalances	N/A
4.3	D.3	Integrated automatic separation system	P
4.4	D.4	Operating ranges	--
4.4.1	D.4.1	Operating frequency range	P
4.4.1	D.4.2	Maximum admissible power reduction in case of underfrequency	P
4.4.2	D.4.3	Continuous operating voltage range	P
4.5	D.5	Immunity to disturbance	--
4.5.1	D.5.1	RoCoF immunity	P
4.5.2	D.5.2	Under-voltage ride through UVRT	N/A
4.5.2	D.5.3	Over-voltage ride through (OVRT)	N/A
4.6	D.6	Active response to frequency deviations	--
4.6.1	D.6.1	Power response to overfrequency	P
4.6.2	D.6.2	Power response to underfrequency	P
4.7	D.7	Power response to voltage changes	--
4.7.1	D.7.1	Q(P) Capabilities	P
4.7.2	D.7.1	Q(U) capabilities	P
4.7.3	D.7.1	Cos φ setpoint	P
4.7.4	D.7.1	Cos φ(P) capabilities	P
4.7.5	D.7.1.1	Specific for a small power-generating plant	P
4.7.6	D.7.1.2	Specific for another (not small) power-generating plant	N/A
4.7.7	D.7.2	Voltage related active power reduction P(U)	P
4.7.8	D.7.3	Provision of additional fast reactive current during faults and voltage steps	N/A
4.8	D.8	Connection and starting to generate electrical power	--
4.8.1	--	Automatic reconnection after tripping	P
4.8.2	--	Starting to generate electrical power	P
4.9	D.9	Ceasing and reduction of active power on set point	--
4.9.1	4.9.1	Ceasing active power	P
4.9.2	4.9.2	Reduction of active power on set point	N/A
4.10	D.10	Communication – Remote monitoring and control	N/A

Note: The declaration of conformity has been evaluated taking into account the IEC Guide 115.

4 TEST RESULTS

4.1 AUTOMATIC SEPARATION SYSTEM

The grid parameters for the connection point of the EUT (Measured at LV side of the transformer) are offered below.

Each power-generating unit must be equipped with an automatic separation system.

This automatic separation system can be either integrated in the power-generating unit itself (which is generally the case), or external to it. When using an external system,

- it must have a “single fault tolerance” according to EN 50549-1, and
- it must be of a type approved by Synergrid, as listed in the C10/21 list of Synergrid published on the website http://www.synergrid.be/download.cfm?fileId=C10-21_DecouplingRelays_NF_20200515.pdf

According to user’s manual, an external AC relays needs to be installed on at the final plant. This external realy, as defined on the user’s manual on page 20, must be approved by Synergrid:

For Belgium, one of the following links is required for external AC relays.

http://www.synergrid.be/download.cfm?fileId=C10-21_DecouplingRelays_NF_20200515.pdf

4.2 POWER QUALITY.

The test has been done according to the clause 8.2 of the standard. The grid parameters for the connection point of the EUT (Measured at LV side of the transformer) are offered below.

R (Ω)	X (Ω)	Z (Ω)	Ψ (°)	S _k /S _n
0.24	0.15	0.39	0.04	10

4.2.1 Rapid voltage changes

The test method is according to VDE-AR-N 4105:2018-11. During operation, any sudden power variation may not influence the voltage level at the point of connection by more than 3%.

$$\Delta u_{\max} \leq 3 \%$$

$$\Delta u_{\max} = k_{\text{imax}} \frac{S_{\text{Emax}}}{S_{\text{kV}}} = \frac{I_{\text{a}}}{I_{\text{rE}}} \cdot \frac{S_{\text{Emax}}}{S_{\text{kV}}}$$

- S_{Emax} is the maximum apparent power of inverter.
- S_{kV} is the network short circuit power.
- I_a is starting current
- I_{rE} is rated current

$$k_{\text{imax}} = \frac{I_{\text{a}}}{I_{\text{rE}}}$$

Used settings of the measurement device for this measurement:

Measurement device	Date of measurement	Recording	Sampling frequency
PA3000	2020/12/30	100ms values	10kHz

The following are the result for calculated k_i

Making operation at reference conditions (of primary energy carrier)	k_i	0.046
Worst case at switch over of generator sections	k_i	--(*)
Making operation without default (of primary energy carrier)	k_i	--(*)
Breaking operation at nominal power	k_i	0.238
Worst-case value of all switching operations	$k_{i\max}$	0.238

(*) Due to the input side is batteries, the voltage will not rapid changed.


According to the performed tests, the Skv minimum for with the inverter can be installed is 60kVA.

After calculating:

$\Delta_{\max} = 1.19\%$


The information provided above should be taken into account for the particular conditions of the installation of the inverter.

**Making operation at reference conditions (of primary energy carrier)
(Normal start working)**



$$k_i = I_a / I_{re} = 0.046$$

**Breaking operation at nominal power
(PV input shut down)**



$$k_i = I_a / I_{re} = 0.238$$

4.2.2 Flickers

The aim of this test is to determine the flicker coefficient c as a function of the grid impedance phase angle.

This requirement is according to point 8.2.3 of the standard. It applies to both PV and storage systems.

The measurements of voltage fluctuations have been measured at 33 %, 66 % and 100 % of the nominal power value of the inverter according to the standard IEC 61000-3-11.

Used settings of the measurement device for this measurement:

Measurement device	Date of measurement	Recording	Sampling frequency
PA3000	2020/11/20, 2020/11/21	100ms values	10kHz

Each step of this test running for 10 minutes, total of 12 steps:

The values took of the most unfavorable of the 12 steps.

Test at 33 %Pn		
Pbin (%)	Limit	Test Value
P _{ST}	≤ 1.0	0.061
P _{LT}	≤ 0.65	0.054
dc	≤ 3.30 %	0.108%
dmax	4 %	0.219%

Test at 66 %Pn		
Pbin (%)	Limit	Test Value
P _{ST}	≤ 1.0	0.062
P _{LT}	≤ 0.65	0.058
dc	≤ 3.30 %	0.108%
dmax	4 %	0.205%

Test at 100%Pn		
Pbin (%)	Limit	Test Value
P _{ST}	≤ 1.0	0.207
P _{LT}	≤ 0.65	0.204
dc	≤ 3.30 %	0.089%
dmax	4 %	0.246%

Test at 33 %Pn

Flicker Mode
Flicker

Range Over

U1	U2	U3	U4	U5	U6	U7
I1	I2	I3	I4	I5	I6	I7

SCL Line Filter

AVG Freq Filter

PA_00023.tif

CH: 1 2 3

4 5 6 7

Count 12/12 Complete

Interval 00:00s/10:00s

Element 1

Volt Range 600 V/50Hz

Un (U1) 231.214V

Freq (U1) 50.000Hz

Dmin 0.10%

	dc[%]	dmax[%]	d(t)[ms]	Pst	Plt			
Limit	3.30	4.00	500 3.00%	1.00	0.65 N:12			
No. 1	0.095	Pass	0.148	Pass	0.0	Pass	0.041	Pass
2	0.092	Pass	0.138	Pass	0.0	Pass	0.035	Pass
3	0.105	Pass	0.130	Pass	0.0	Pass	0.049	Pass
4	0.105	Pass	0.156	Pass	0.0	Pass	0.056	Pass
5	0.099	Pass	0.219	Pass	0.0	Pass	0.055	Pass
6	0.101	Pass	0.135	Pass	0.0	Pass	0.055	Pass
7	0.106	Pass	0.140	Pass	0.0	Pass	0.057	Pass
8	0.102	Pass	0.150	Pass	0.0	Pass	0.056	Pass
9	0.100	Pass	0.142	Pass	0.0	Pass	0.056	Pass
10	0.108	Pass	0.142	Pass	0.0	Pass	0.058	Pass
11	0.102	Pass	0.134	Pass	0.0	Pass	0.061	Pass
12	0.100	Pass	0.147	Pass	0.0	Pass	0.060	Pass
Result		Pass		Pass		Pass	0.054	Pass

Update: 3723

Runtime: 4:44:31

39% 10% x1

2020-11-21 14:15:58

ΣA(3P4W)

U1 1000 V
I1 50 A
Sync Src: U1
Integral: Reset

U2 1000 V
I2 50 A
Sync Src: U1
Integral: Reset

U3 1000 V
I3 50 A
Sync Src: U1
Integral: Reset

Element 4

U4 1000 V
I4 50 A
Sync Src: U1
Integral: Reset

Element 5

U5 1000 V
I5 5 A
Sync Src: U1
Integral: Reset

Test at 66 %Pn

Flicker Mode
Flicker

Range Over

U1	U2	U3	U4	U5	U6	U7
I1	I2	I3	I4	I5	I6	I7

SCL Line Filter

AVG Freq Filter

CH: 1 2 3

4 5 6 7

Count 12/12 Complete

Interval 00:00s/10:00s

Element 1

Volt Range 600 V/50Hz

Un (U1) 231.388V

Freq (U1) 50.000Hz

Dmin 0.10%

	dc[%]	dmax[%]	d(t)[ms]	Pst	Plt			
Limit	3.30	4.00	500 3.00%	1.00	0.65 N:12			
No. 1	0.093	Pass	0.151	Pass	0.0	Pass	0.056	Pass
2	0.098	Pass	0.135	Pass	0.0	Pass	0.062	Pass
3	0.108	Pass	0.194	Pass	0.0	Pass	0.060	Pass
4	0.096	Pass	0.170	Pass	0.0	Pass	0.059	Pass
5	0.106	Pass	0.147	Pass	0.0	Pass	0.058	Pass
6	0.099	Pass	0.205	Pass	0.0	Pass	0.059	Pass
7	0.104	Pass	0.142	Pass	0.0	Pass	0.058	Pass
8	0.098	Pass	0.137	Pass	0.0	Pass	0.056	Pass
9	0.099	Pass	0.134	Pass	0.0	Pass	0.056	Pass
10	0.101	Pass	0.134	Pass	0.0	Pass	0.056	Pass
11	0.101	Pass	0.164	Pass	0.0	Pass	0.056	Pass
12	0.099	Pass	0.194	Pass	0.0	Pass	0.055	Pass
Result		Pass		Pass		Pass	0.058	Pass

Update: 4193

Runtime: 8:19:18

39% 10% x1

2020-11-21 10:35:36

ΣA(3P4W)

U1 1000 V
I1 50 A
Sync Src: U1
Integral: Reset

U2 1000 V
I2 50 A
Sync Src: U1
Integral: Reset

U3 1000 V
I3 50 A
Sync Src: U1
Integral: Reset

Element 4

U4 1000 V
I4 50 A
Sync Src: U1
Integral: Reset

Element 5

U5 1000 V
I5 5 A
Sync Src: U1
Integral: Reset

Test at 100 %Pn

Flicker Mode
Flicker

Range Over

U1	U2	U3	U4	U5	U6	U7
I1	I2	I3	I4	I5	I6	I7

SCL

Line Filter

AVG

Freq Filter

CH: 1 2 3

4 5 6 7

Count 12/12 Complete

Interval 00:00s/10:00s

Element 1

Volt Range	600 V/50Hz	Element1	Judgement	Pass
Un (U1)	231.388V	Total	Judgement	Pass
Freq (U1)	50.000Hz	(Element1)		
Dmin	0.10%			

	dc[%]		dmax[%]		d(t)[ms]		Pst		PIt
Limit	3.30		4.00		500 3.00%		1.00		0.65 N:12
No. 1	0.070	Pass	0.246	Pass	0.0	Pass	0.205	Pass	
2	0.074	Pass	0.210	Pass	0.0	Pass	0.204	Pass	
3	0.070	Pass	0.230	Pass	0.0	Pass	0.204	Pass	
4	0.057	Pass	0.169	Pass	0.0	Pass	0.204	Pass	
5	0.068	Pass	0.218	Pass	0.0	Pass	0.204	Pass	
6	0.089	Pass	0.197	Pass	0.0	Pass	0.207	Pass	
7	0.073	Pass	0.179	Pass	0.0	Pass	0.204	Pass	
8	0.074	Pass	0.175	Pass	0.0	Pass	0.204	Pass	
9	0.065	Pass	0.191	Pass	0.0	Pass	0.206	Pass	
10	0.081	Pass	0.198	Pass	0.0	Pass	0.203	Pass	
11	0.080	Pass	0.201	Pass	0.0	Pass	0.206	Pass	
12	0.080	Pass	0.234	Pass	0.0	Pass	0.203	Pass	
Result		Pass		Pass		Pass		Pass	0.204 Pass

Update: 4008

Runtime: 4:52:11

38% 10% x1 2020-11-20 13:51:24

Element 1

U1 600 V

I1 50 A

Sync Src: U1

Integral: Reset

Element 2

U2 1000 V

I2 50 A

Sync Src: U1

Integral: Reset

Element 3

U3 1000 V

I3 50 A

Sync Src: U1

Integral: Reset

Element 4

U4 1000 V

I4 50 A

Sync Src: U1

Integral: Reset

Element 5

U5 1000 V

I5 50 A

Sync Src: U1

Integral: Reset

4.2.3 Harmonic

The aim of this test is to determine relevant values for PGU continuous operation.

Test performed according to point 8.2.4 of the standard. It can be applied at both PV and storage systems.

The reactive power setpoint is 0 VAR, the harmonics have been measured 5 minutes average values of line to neutral current.

They have been verified limits at different power levels, from 10%Pn to 100% Pn, in 10%Pn steps.

The arithmetic average is formed over the 10 minutes record for each harmonic, interharmonic and higher frequency component of the current.

The total distortion of the current harmonics (TDC) has been calculated according to standard:

$$TDC = \frac{\sqrt{\sum_{h=2}^{50} I_h^2}}{I_n} \cdot 100$$

See point (Definitions) of this report.

The total distortion of the voltage harmonics (TDD) has been determined using the same procedure.

NOTE: According to Standard, the requirements for Harmonics test are applicable at plant level (according to Synergrid technical prescriptions C10/17(HV connection) and C10/19 (LV connection)), the results shown in this chapter are performed at inverter level. The results shown are informative.

- | | |
|-------------------------------|---|
| • PGU operation mode; Q (VAr) | Q setpoint = 0 VAr |
| • Voltage range (V) | 230 V |
| • Voltage unbalance | Same conditions as point 4.2.4 of this test report (*)
(Umbalance Chapter) |
| • Measured period (min) | 5 min each active power level |

(*) As the test procedure for both tests is similar, representing the inverter working in continuous operation in a wide range of power bins, it is considered that the voltage unbalance conditions will be similar at both tests.

Power bin (%Pn)	Number of records
2 %	1
10 %	1
20 %	1
30 %	1
40 %	1
50 %	1
60 %	1
70 %	1
80 %	1
90 %	1
100 %	1


Used settings of the measurement device for this measurement:

Measurement device	Date of measurement	Recording	Sampling frequency
PA5000H	2021/1/5	100ms values	10kHz


4.2.3.1 Current harmonics

P_n (%)	2	10	20	30	40	50	60	70	80	90	100	Max (%)
Nr./ Order	I_h(%)	I_h(%)	I_h(%)	I_h(%)	I_h(%)	I_h(%)	I_h(%)	I_h(%)	I_h(%)	I_h(%)	I_h(%)	
2	0.014	0.038	0.063	0.085	0.075	0.080	0.115	0.170	0.214	0.193	0.173	0.214
3	0.426	0.619	0.664	0.718	0.696	0.733	0.711	0.729	0.720	0.744	0.721	0.744
4	0.048	0.056	0.043	0.056	0.052	0.075	0.068	0.086	0.090	0.090	0.075	0.090
5	0.272	0.266	0.334	0.310	0.344	0.342	0.360	0.379	0.392	0.410	0.422	0.422
6	0.011	0.024	0.037	0.030	0.044	0.054	0.055	0.043	0.064	0.066	0.063	0.066
7	0.191	0.196	0.190	0.201	0.244	0.248	0.295	0.294	0.337	0.353	0.390	0.390
8	0.008	0.028	0.038	0.032	0.034	0.041	0.044	0.051	0.053	0.050	0.061	0.061
9	0.104	0.122	0.098	0.143	0.226	0.260	0.284	0.342	0.348	0.379	0.394	0.394
10	0.011	0.022	0.030	0.033	0.037	0.046	0.036	0.041	0.058	0.067	0.061	0.067
11	0.062	0.078	0.089	0.156	0.187	0.292	0.281	0.338	0.363	0.409	0.412	0.412
12	0.018	0.022	0.037	0.028	0.034	0.033	0.052	0.030	0.039	0.051	0.062	0.062
13	0.041	0.063	0.082	0.142	0.189	0.247	0.323	0.309	0.384	0.370	0.430	0.430
14	0.022	0.026	0.033	0.046	0.046	0.039	0.056	0.059	0.053	0.068	0.055	0.068
15	0.034	0.043	0.062	0.164	0.205	0.230	0.300	0.336	0.339	0.394	0.387	0.394
16	0.011	0.025	0.034	0.018	0.030	0.027	0.034	0.029	0.034	0.043	0.043	0.043
17	0.015	0.029	0.053	0.154	0.209	0.234	0.258	0.321	0.325	0.359	0.383	0.383
18	0.011	0.023	0.037	0.026	0.030	0.036	0.035	0.029	0.043	0.034	0.031	0.043
19	0.041	0.035	0.045	0.125	0.168	0.199	0.224	0.261	0.303	0.295	0.339	0.339
20	0.007	0.015	0.019	0.021	0.022	0.029	0.024	0.030	0.033	0.036	0.040	0.040
21	0.015	0.030	0.043	0.109	0.154	0.194	0.208	0.228	0.262	0.282	0.278	0.282
22	0.008	0.012	0.019	0.022	0.026	0.023	0.022	0.014	0.024	0.029	0.022	0.029
23	0.043	0.034	0.023	0.083	0.125	0.159	0.186	0.200	0.216	0.247	0.245	0.247
24	0.010	0.012	0.026	0.029	0.025	0.025	0.018	0.033	0.018	0.029	0.034	0.034
25	0.013	0.021	0.026	0.072	0.111	0.142	0.163	0.179	0.187	0.197	0.221	0.221
26	0.016	0.016	0.032	0.034	0.033	0.033	0.036	0.032	0.039	0.036	0.039	0.039
27	0.015	0.018	0.016	0.057	0.084	0.108	0.126	0.144	0.151	0.160	0.173	0.173
28	0.006	0.009	0.018	0.016	0.018	0.022	0.022	0.031	0.028	0.029	0.034	0.034
29	0.014	0.014	0.016	0.051	0.076	0.099	0.112	0.123	0.134	0.135	0.145	0.145
30	0.007	0.011	0.014	0.013	0.012	0.013	0.010	0.018	0.018	0.020	0.017	0.020
31	0.033	0.042	0.025	0.043	0.054	0.076	0.094	0.105	0.117	0.123	0.124	0.124
32	0.014	0.019	0.019	0.016	0.014	0.014	0.014	0.014	0.017	0.015	0.015	0.019
33	0.051	0.051	0.040	0.046	0.052	0.067	0.087	0.095	0.105	0.107	0.116	0.116
34	0.017	0.011	0.014	0.016	0.015	0.016	0.015	0.026	0.015	0.023	0.018	0.026
35	0.027	0.034	0.036	0.036	0.042	0.053	0.064	0.075	0.081	0.093	0.092	0.093
36	0.010	0.012	0.011	0.013	0.016	0.015	0.013	0.012	0.013	0.017	0.014	0.017
37	0.050	0.044	0.047	0.044	0.039	0.046	0.055	0.067	0.076	0.082	0.087	0.087
38	0.014	0.010	0.015	0.013	0.014	0.019	0.012	0.025	0.018	0.021	0.020	0.025
39	0.049	0.043	0.036	0.035	0.030	0.033	0.045	0.054	0.061	0.069	0.071	0.071
40	0.010	0.013	0.010	0.010	0.013	0.015	0.019	0.019	0.018	0.022	0.024	0.024
41	0.050	0.050	0.041	0.037	0.027	0.037	0.048	0.058	0.066	0.074	0.077	0.077
42	0.008	0.009	0.008	0.010	0.011	0.009	0.008	0.011	0.010	0.013	0.013	0.013
43	0.044	0.048	0.039	0.042	0.027	0.026	0.034	0.043	0.053	0.058	0.063	0.063
44	0.008	0.014	0.012	0.013	0.013	0.016	0.018	0.020	0.022	0.025	0.025	0.025
45	0.043	0.036	0.040	0.036	0.027	0.032	0.043	0.051	0.059	0.072	0.069	0.072
46	0.006	0.010	0.008	0.011	0.013	0.010	0.009	0.009	0.008	0.012	0.012	0.013
47	0.058	0.046	0.046	0.044	0.027	0.026	0.030	0.037	0.048	0.050	0.059	0.059
48	0.009	0.011	0.009	0.010	0.009	0.013	0.011	0.015	0.015	0.018	0.021	0.021
49	0.054	0.050	0.045	0.040	0.032	0.030	0.039	0.047	0.050	0.062	0.058	0.062
50	0.008	0.008	0.009	0.009	0.012	0.011	0.009	0.008	0.009	0.012	0.011	0.012
TDC (%)	0.584	0.745	0.812	0.923	0.999	1.109	1.182	1.278	1.351	1.425	1.465	1.465

Current Harmonics



Total Distortion Current Harmonic




4.2.3.2 Voltage harmonics


Measurements of voltage harmonics at continuous operation are done according to IEC 61000-4-7:2002

P_n (%)	2	10	20	30	40	50	60	70	80	90	100	Max (%)
Nr./ Order	U_h (%)	U_h (%)	U_h (%)	U_h (%)	U_h (%)	U_h (%)	U_h (%)	U_h (%)	U_h (%)	U_h (%)	U_h (%)	
2	0.007	0.008	0.008	0.007	0.010	0.010	0.012	0.009	0.010	0.013	0.012	0.013
3	0.045	0.042	0.039	0.038	0.035	0.032	0.033	0.030	0.032	0.032	0.032	0.045
4	0.005	0.005	0.005	0.005	0.005	0.005	0.005	0.005	0.005	0.005	0.005	0.005
5	0.035	0.031	0.026	0.025	0.022	0.020	0.017	0.017	0.018	0.019	0.017	0.035
6	0.005	0.004	0.004	0.004	0.005	0.004	0.005	0.004	0.005	0.004	0.005	0.005
7	0.021	0.018	0.014	0.015	0.016	0.015	0.016	0.017	0.018	0.020	0.026	0.026
8	0.003	0.003	0.003	0.003	0.003	0.003	0.003	0.004	0.004	0.003	0.004	0.004
9	0.012	0.010	0.011	0.013	0.015	0.016	0.017	0.018	0.019	0.019	0.017	0.019
10	0.004	0.004	0.004	0.004	0.004	0.004	0.004	0.004	0.004	0.005	0.005	0.005
11	0.010	0.012	0.015	0.015	0.015	0.016	0.016	0.016	0.016	0.016	0.017	0.017
12	0.003	0.003	0.003	0.003	0.003	0.003	0.004	0.003	0.003	0.004	0.004	0.004
13	0.014	0.017	0.017	0.015	0.014	0.013	0.013	0.012	0.012	0.011	0.013	0.017
14	0.003	0.003	0.004	0.004	0.004	0.004	0.005	0.005	0.005	0.005	0.005	0.005
15	0.017	0.020	0.020	0.016	0.013	0.010	0.009	0.009	0.010	0.012	0.013	0.020
16	0.004	0.004	0.004	0.004	0.004	0.004	0.004	0.004	0.004	0.004	0.004	0.004
17	0.018	0.020	0.018	0.012	0.009	0.007	0.007	0.010	0.012	0.015	0.018	0.020
18	0.003	0.004	0.004	0.004	0.004	0.004	0.004	0.004	0.004	0.004	0.004	0.004
19	0.019	0.020	0.017	0.012	0.007	0.006	0.008	0.012	0.016	0.017	0.021	0.021
20	0.004	0.004	0.004	0.004	0.004	0.004	0.004	0.004	0.004	0.004	0.004	0.004
21	0.017	0.018	0.014	0.009	0.006	0.009	0.011	0.013	0.018	0.020	0.021	0.021
22	0.004	0.004	0.004	0.003	0.004	0.004	0.004	0.004	0.004	0.004	0.003	0.004
23	0.015	0.015	0.011	0.006	0.007	0.010	0.014	0.016	0.017	0.021	0.019	0.021
24	0.004	0.004	0.004	0.004	0.003	0.004	0.003	0.004	0.003	0.004	0.004	0.004
25	0.011	0.012	0.009	0.006	0.009	0.012	0.014	0.015	0.017	0.018	0.021	0.021
26	0.004	0.004	0.005	0.004	0.004	0.004	0.004	0.004	0.004	0.003	0.004	0.005
27	0.006	0.008	0.007	0.008	0.011	0.014	0.016	0.017	0.017	0.018	0.018	0.018
28	0.004	0.004	0.004	0.004	0.003	0.003	0.004	0.004	0.004	0.003	0.004	0.004
29	0.006	0.006	0.008	0.011	0.013	0.015	0.017	0.017	0.018	0.016	0.018	0.018
30	0.004	0.004	0.004	0.004	0.004	0.004	0.004	0.004	0.004	0.004	0.004	0.004
31	0.006	0.005	0.008	0.010	0.012	0.015	0.016	0.016	0.015	0.016	0.014	0.016
32	0.005	0.006	0.005	0.005	0.005	0.005	0.004	0.004	0.005	0.005	0.005	0.006
33	0.008	0.008	0.011	0.012	0.014	0.015	0.016	0.015	0.016	0.015	0.016	0.016
34	0.005	0.004	0.004	0.004	0.004	0.005	0.005	0.005	0.004	0.005	0.004	0.005
35	0.011	0.011	0.012	0.012	0.014	0.015	0.015	0.016	0.014	0.016	0.014	0.016
36	0.005	0.006	0.005	0.006	0.006	0.006	0.005	0.004	0.005	0.005	0.005	0.006
37	0.012	0.011	0.013	0.012	0.013	0.013	0.014	0.013	0.015	0.014	0.015	0.015
38	0.005	0.004	0.004	0.004	0.005	0.005	0.004	0.005	0.005	0.005	0.004	0.005
39	0.012	0.010	0.011	0.009	0.010	0.012	0.012	0.013	0.012	0.013	0.012	0.013
40	0.005	0.005	0.005	0.005	0.006	0.005	0.005	0.005	0.005	0.005	0.005	0.006
41	0.012	0.013	0.013	0.012	0.012	0.013	0.013	0.013	0.015	0.014	0.015	0.015
42	0.005	0.004	0.004	0.004	0.005	0.005	0.005	0.005	0.004	0.005	0.005	0.005
43	0.013	0.012	0.011	0.009	0.009	0.010	0.012	0.013	0.012	0.013	0.013	0.013
44	0.004	0.004	0.004	0.004	0.005	0.005	0.004	0.004	0.004	0.004	0.005	0.005
45	0.011	0.012	0.011	0.010	0.010	0.011	0.011	0.011	0.013	0.013	0.014	0.014
46	0.004	0.004	0.004	0.004	0.004	0.004	0.004	0.004	0.004	0.004	0.004	0.004
47	0.013	0.011	0.010	0.009	0.008	0.009	0.011	0.012	0.012	0.013	0.013	0.013
48	0.005	0.005	0.004	0.005	0.005	0.005	0.004	0.005	0.005	0.005	0.005	0.005
49	0.010	0.010	0.010	0.009	0.008	0.009	0.009	0.010	0.011	0.011	0.013	0.013
50	0.003	0.003	0.003	0.003	0.004	0.003	0.003	0.003	0.003	0.004	0.004	0.004
TDD (%)	0.086	0.085	0.079	0.074	0.072	0.073	0.076	0.077	0.082	0.086	0.090	0.090

Voltage Harmonics



Total Voltage Distortion




4.2.3.3 Interharmonics at continuous operation

Test performed according to point 8.2 of the standard.

Measurements of interharmonics at continuous operation are done according to IEC 61000-4-7:2002.

P_n (%)	2	10	20	30	40	50	60	70	80	90	100	MAX
F [Hz]	I_h(%)	I_h(%)	I_h(%)	I_h(%)	I_h(%)	I_h(%)	I_h(%)	I_h(%)	I_h(%)	I_h(%)	I_h(%)	(%)
75	0.026	0.085	0.143	0.197	0.224	0.315	0.389	0.431	0.499	0.504	0.529	0.529
125	0.014	0.035	0.045	0.072	0.059	0.080	0.100	0.096	0.175	0.126	0.114	0.175
175	0.015	0.034	0.051	0.056	0.055	0.063	0.064	0.093	0.117	0.100	0.068	0.117
225	0.014	0.028	0.047	0.055	0.052	0.058	0.067	0.074	0.100	0.089	0.062	0.100
275	0.013	0.025	0.042	0.039	0.042	0.047	0.041	0.043	0.067	0.058	0.046	0.067
325	0.013	0.022	0.043	0.039	0.046	0.050	0.050	0.045	0.062	0.067	0.054	0.067
375	0.013	0.026	0.046	0.041	0.043	0.061	0.068	0.065	0.063	0.047	0.069	0.069
425	0.012	0.028	0.041	0.040	0.040	0.051	0.062	0.067	0.061	0.045	0.061	0.067
475	0.012	0.028	0.038	0.044	0.049	0.050	0.052	0.067	0.079	0.072	0.051	0.079
525	0.012	0.027	0.032	0.038	0.042	0.046	0.043	0.055	0.070	0.059	0.050	0.070
575	0.011	0.026	0.034	0.033	0.042	0.055	0.056	0.043	0.057	0.064	0.062	0.064
625	0.011	0.022	0.030	0.031	0.035	0.044	0.049	0.041	0.047	0.053	0.051	0.053
675	0.011	0.021	0.030	0.033	0.032	0.040	0.054	0.051	0.050	0.039	0.046	0.054
725	0.012	0.020	0.029	0.030	0.031	0.034	0.042	0.047	0.047	0.037	0.040	0.047
775	0.011	0.020	0.026	0.028	0.033	0.037	0.039	0.043	0.051	0.048	0.045	0.051
825	0.011	0.021	0.025	0.025	0.029	0.035	0.032	0.035	0.043	0.039	0.039	0.043
875	0.011	0.023	0.023	0.023	0.028	0.030	0.034	0.034	0.036	0.042	0.037	0.042
925	0.013	0.019	0.022	0.022	0.025	0.029	0.029	0.033	0.033	0.037	0.034	0.037
975	0.014	0.020	0.022	0.022	0.025	0.029	0.027	0.033	0.036	0.029	0.035	0.036
1025	0.011	0.016	0.019	0.019	0.022	0.026	0.025	0.028	0.033	0.028	0.030	0.033
1075	0.013	0.018	0.020	0.021	0.023	0.027	0.027	0.024	0.034	0.032	0.027	0.034
1125	0.010	0.015	0.018	0.017	0.021	0.024	0.024	0.022	0.029	0.028	0.025	0.029
1175	0.010	0.015	0.017	0.017	0.020	0.021	0.021	0.021	0.023	0.031	0.024	0.031
1225	0.011	0.016	0.017	0.018	0.021	0.021	0.021	0.025	0.024	0.027	0.027	0.027
1275	0.010	0.014	0.015	0.016	0.017	0.019	0.020	0.023	0.023	0.021	0.026	0.026
1325	0.010	0.014	0.015	0.016	0.017	0.019	0.021	0.021	0.025	0.022	0.025	0.025
1375	0.010	0.013	0.014	0.014	0.016	0.017	0.019	0.018	0.021	0.020	0.022	0.022
1425	0.010	0.013	0.014	0.015	0.016	0.017	0.019	0.020	0.022	0.021	0.022	0.022
1475	0.009	0.013	0.013	0.014	0.015	0.016	0.016	0.019	0.018	0.019	0.018	0.019
1525	0.009	0.012	0.013	0.014	0.015	0.016	0.016	0.019	0.020	0.020	0.019	0.020
1575	0.009	0.012	0.012	0.013	0.014	0.015	0.015	0.017	0.020	0.017	0.016	0.020
1625	0.010	0.012	0.012	0.013	0.014	0.016	0.016	0.017	0.020	0.018	0.018	0.020
1675	0.011	0.013	0.013	0.013	0.014	0.015	0.015	0.017	0.018	0.016	0.017	0.018
1725	0.010	0.012	0.012	0.013	0.013	0.014	0.014	0.017	0.017	0.017	0.017	0.017
1775	0.011	0.013	0.012	0.013	0.013	0.014	0.015	0.016	0.016	0.018	0.016	0.018
1825	0.010	0.011	0.012	0.012	0.013	0.014	0.014	0.015	0.016	0.016	0.016	0.016
1875	0.009	0.011	0.011	0.011	0.012	0.013	0.013	0.014	0.016	0.016	0.016	0.016
1925	0.010	0.011	0.012	0.012	0.014	0.014	0.014	0.015	0.017	0.017	0.016	0.017
1975	0.010	0.011	0.012	0.011	0.012	0.013	0.013	0.014	0.015	0.015	0.014	0.015




4.2.3.4 Higher frequency components

Test performed according to point 8.2 of the standard.

Measurements of Higher frequency are done according to IEC 61000-4-7:2002.

P _{bin} (%)	2	10	20	30	40	50	60	70	80	90	100	MAX
F [kHz]	I _h (%)	I _h (%)	I _h (%)	I _h (%)	I _h (%)	I _h (%)	I _h (%)	I _h (%)	I _h (%)	I _h (%)	I _h (%)	(%)
2.1	0.071	0.075	0.063	0.063	0.049	0.057	0.068	0.081	0.093	0.103	0.108	0.108
2.3	0.076	0.065	0.065	0.062	0.048	0.051	0.060	0.070	0.083	0.094	0.098	0.098
2.5	0.089	0.081	0.075	0.067	0.054	0.052	0.056	0.067	0.075	0.083	0.086	0.089
2.7	0.080	0.067	0.073	0.065	0.059	0.053	0.059	0.067	0.076	0.085	0.085	0.085
2.9	0.069	0.062	0.064	0.059	0.056	0.050	0.049	0.053	0.062	0.068	0.069	0.069
3.1	0.058	0.046	0.051	0.052	0.053	0.047	0.044	0.047	0.051	0.056	0.058	0.058
3.3	0.050	0.040	0.045	0.046	0.048	0.044	0.041	0.043	0.047	0.050	0.056	0.056
3.5	0.048	0.041	0.043	0.045	0.047	0.045	0.044	0.044	0.048	0.051	0.055	0.055
3.7	0.047	0.041	0.043	0.044	0.047	0.044	0.042	0.042	0.045	0.047	0.050	0.050
3.9	0.044	0.040	0.040	0.040	0.041	0.041	0.040	0.039	0.040	0.041	0.043	0.044
4.1	0.038	0.037	0.035	0.036	0.038	0.036	0.036	0.035	0.037	0.038	0.040	0.040
4.3	0.036	0.036	0.033	0.034	0.034	0.034	0.033	0.033	0.034	0.034	0.036	0.036
4.5	0.040	0.041	0.038	0.037	0.037	0.037	0.037	0.036	0.036	0.036	0.037	0.041
4.7	0.086	0.083	0.081	0.080	0.079	0.078	0.076	0.074	0.073	0.070	0.069	0.086
4.9	0.088	0.087	0.084	0.082	0.082	0.080	0.078	0.076	0.074	0.072	0.070	0.088
5.1	0.043	0.042	0.041	0.040	0.041	0.040	0.040	0.039	0.039	0.038	0.040	0.043
5.3	0.042	0.041	0.041	0.041	0.041	0.040	0.040	0.039	0.039	0.038	0.040	0.042
5.5	0.047	0.046	0.046	0.045	0.045	0.045	0.044	0.043	0.042	0.041	0.043	0.047
5.7	0.077	0.073	0.072	0.073	0.071	0.070	0.069	0.066	0.065	0.061	0.061	0.077
5.9	0.075	0.073	0.074	0.071	0.071	0.069	0.067	0.065	0.063	0.060	0.060	0.075
6.1	0.047	0.046	0.046	0.046	0.046	0.045	0.044	0.043	0.042	0.041	0.042	0.047
6.3	0.047	0.045	0.045	0.045	0.045	0.045	0.044	0.043	0.042	0.041	0.042	0.047
6.5	0.049	0.048	0.048	0.048	0.049	0.047	0.047	0.046	0.045	0.044	0.045	0.049
6.7	0.047	0.045	0.045	0.045	0.046	0.045	0.045	0.044	0.043	0.042	0.044	0.047
6.9	0.055	0.053	0.053	0.053	0.053	0.053	0.052	0.051	0.051	0.050	0.050	0.055
7.1	0.049	0.047	0.047	0.048	0.048	0.048	0.049	0.048	0.048	0.048	0.049	0.049
7.3	0.047	0.044	0.044	0.045	0.046	0.046	0.046	0.045	0.044	0.044	0.045	0.047
7.5	0.049	0.046	0.046	0.047	0.047	0.047	0.046	0.046	0.046	0.046	0.046	0.049
7.7	0.047	0.043	0.043	0.044	0.045	0.044	0.044	0.044	0.044	0.043	0.044	0.047
7.9	0.044	0.041	0.041	0.042	0.042	0.042	0.042	0.042	0.041	0.041	0.041	0.044
8.1	0.046	0.043	0.043	0.045	0.045	0.045	0.045	0.045	0.045	0.044	0.044	0.046
8.3	0.062	0.060	0.062	0.064	0.065	0.067	0.069	0.071	0.073	0.074	0.078	0.078
8.5	0.047	0.044	0.044	0.045	0.045	0.045	0.045	0.045	0.044	0.044	0.043	0.047
8.7	0.041	0.038	0.038	0.039	0.039	0.038	0.038	0.037	0.037	0.036	0.037	0.041
8.9	0.037	0.034	0.034	0.035	0.036	0.035	0.035	0.034	0.034	0.033	0.033	0.037

Current high frequency harmonics



4.2.4 Unbalances

The aim of this test is to determinate the unbalance in the PGU's fed-in current.

Requirements according to point 8.2.5 of the standard.

They have been determined the unbalance between positive and negative sequences for currents (U_i) using following equation:

$$U_i = (I_{1-} / I_{1+}) \cdot 100 \%$$

It is not applicable because the EUT is single phase output inverter.

4.3 INTEGRATED AUTOMATIC SEPARATION SYSTEM

These tests have been done according to chapter D.3 of the standard. The aim is to verify the protection settings of the EUT for both voltage and frequency.

It has been tested, for both frequency and voltage, two different protection stages for both undervoltage/underfrequency and overvoltage/overfrequency.

It has to be tested also a 10 min mean overvoltage protection stage which function shall be based on the calculation of the square root of the arithmetic mean of the squared input values over 10 min. The calculation of a new 10 min value at least every 3s is sufficient, which is then to be compared with the threshold value.

The standard present for each protection stage a defined threshold as well as an operation time response. These configurations are:

Function	Trip setting
Overvoltage 10 min mean	230 V + 10 % no delay*
Overvoltage	230 V +15 % no delay*
Undervoltage	230 V -20 % no delay*
Overfrequency	51,5 Hz no delay*
Underfrequency	47,5 Hz no delay*
LoM	according to EN 62116
<p><i>*« No delay » means that no time delay is added to the intrinsic technical duration required to initiate the disconnection. The operate time may not exceed 200ms.</i></p>	


The compliances with the requirements of clause D.3 of the standard is stated in section 4.6 of following test report:

Used settings of the measurement device for this measurement:

Measurement device	Date of measurement	Recording	Sampling frequency
PA3000	2020/12/30, 2021/1/5, 2021/1/15,	100ms values	10kHz



4.3.1 Overvoltage 10 min mean Test

Test Item	Setting Value	Measured Value	Setting disconnect time	Measured disconnect time
Overvoltage 10 min mean	253.0 V	253.0 V	1 s	1.000 s





4.3.2 Overvoltage Test

Test Item	Setting Value	Measured Value	Measured disconnect time	Limited Disconnect time
Overvoltage	264.5 V	264.4 V	166 ms	200 ms





4.3.3 Undervoltage Test

Test Item	Setting Value	Measured Value	Measured disconnect time	Limited Disconnect time
Undervoltage	184.0 V	184.0 V	164 ms	200 ms





4.3.4 Overfrequency Test

Test Item	Setting Value	Measured Value	Measured disconnect time	Limited Disconnect time
Overfrequency	51.50 Hz	51.50 Hz	161 ms	200 ms



4.3.5 Underfrequency Test

Test Item	Setting Value	Measured Value	Measured disconnect time	Limited Disconnect time
Overfrequency	47.50 Hz	47.49 Hz	181 ms	200 ms



4.3.6 LOM Test


The test has been done according to EN 62116 of the standard. Test A is at full power, Test B is at 66 %Pn, Test C is at 33 %Pn.

Used settings of the measurement device for this measurement:

Measurement device	Date of measurement	Recording	Sampling frequency
PA3000	2021/1/5	100ms values	10kHz
DS05014A	2021/1/5	--	100kHz


4.3.6.1 Active Power > 90 %Pn. Test A

Balanced Load		
M (%)	N (%)	Disconnection (ms) (limit at t=2s)
-5	+5	305
-5	0	220
-5	-5	248
0	+5	322
0	0	332
0	-5	245
+5	+5	282
+5	0	202
+5	-5	167




4.3.6.2 Active Power 50-66 %Pn. Test B

Balanced Load		Disconnection (ms) (limit at t=2s)
M (%)	N (%)	
0	-5	165
0	-4	191
0	-3	169
0	-2	184
0	-1	184
0	0	316
0	+1	220
0	+2	309
0	+3	171
0	+4	202
0	+5	177



4.3.6.3 Active Power 25-33 %Pn. Test C

Balanced Load		
M (%)	N (%)	Disconnection (ms) (limit at t=2s)
0	-5	214
0	-4	249
0	-3	169
0	-2	245
0	-1	209
0	0	290
0	+1	228
0	+2	286
0	+3	281
0	+4	237
0	+5	212



4.4 OPERATING RANGES

4.4.1 Operating frequency range and Maximum admissible power reduction in case of underfrequency

This test has been done according to chapter D.4.1 of the standard. The aim of the test is to verify if the EUT is capable of operating at different frequency ranges without disconnection and power reduction for the amount of time.

According to the standard, the capability of the power-generating unit to operate in the frequency range from 51.5 Hz and 52.5 Hz and, where appropriate, the maximum duration of operation in this frequency range. The additional test performed to verify the capability to work at 52.5Hz.


Note: protective functions for disconnection due to abnormal frequency variations were disabled for the performance of this test.

Used settings of the measurement device for this measurement:


Measurement device	Date of measurement	Recording	Sampling frequency
PA3000	2020/12/30, 2021/1/16	100ms values	10kHz

Test result and graph as following:

Steps	f (Hz) setting	Time requirement	f Measured (Hz)	Time measured (min)	Power measured (p.u.)
1	47.0	> 30 s	47.00	1.1	1.003
2	47.5	> 30 min	47.50	34.9	1.003
3	48.5	> 30 min	48.50	38.6	1.004
4	52.0	> 15 min	52.00	16.8	1.004
5	50.0	> 1 min	50.00	2.3	1.004
6	51.5	> 30 min	51.50	34.5	1.005
7	52.0	> 30 min	52.00	32.8	1.005
8	52.5	> 30 min	52.50	32.5	1.004



For frequencies below 49.0 Hz, according to chapter D.4.2 of the standard, the EUT shall be capable of keeping its active power output constant and not lower than the following characteristic:




According to the standard, following test will perform to verify it.

Parameter	Value
Frequency threshold	49 Hz
Slope	2 %/Hz

Test results are presented in the following table and graphs:

Step	f (Hz)	f Meas. (Hz)	T (s)	P desired (p.u.)	P Meas. (p.u.)	P deviation (p.u.)
1	50.00 ± 0.05	50.00	>30	1.000	1.005	0.005
2	49.50 ± 0.05	50.00	>30	1.000	1.006	0.006
3	49.00 ± 0.05	50.00	>30	1.000	1.006	0.006
4	48.50 ± 0.05	50.00	>30	0.980	0.987	0.007
5	48.00 ± 0.05	50.00	>30	0.960	0.967	0.007
6	47.50 ± 0.05	50.00	>30	0.940	0.947	0.007



4.4.2 Continuous operating voltage range

This test has been done according to chapter D.4.3 of the standard. The aim of the test is to verify that the EUT is capable of operating continuously when the voltage stays inside of following ranges:

- For LV connections: Inside of the range of 85-110%Un.
- For HV connections: Inside of the range of 90-110%Un.


For voltages below 95%Un, it is allowed to reduce apparent power to maintain the current limits of the generating plant. This reduction shall be as small as technically possible.

Used settings of the measurement device for this measurement:

Measurement device	Date of measurement	Recording	Sampling frequency
PA3000	2020/12/31	100ms values	10kHz

In order to verify this function, the parameter setting as following to perform the test:

Step	Voltage (p.u.)	P desired (p.u.)	Time requirement (s)	Time measured (s)	P meas. (p.u.)
1	1.00	1	> 60	99.2	1.000
2	0.85	--	> 120	187.7	0.897
3	1.00	1	> 5	41.2	1.000
4	1.10	1	> 120	120.6	1.001





4.5 IMMUNITY TO DISTURBANCE

4.5.1 RoCoF immunity

This test has been done according to chapter D.5.1 of the standard. The aim of the test is to verify if the EUT is capable of operating without disconnection when submitted to frequency jumps.

The test has been done according following graphs.





Used settings of the measurement device for this measurement:

Measurement device	Date of measurement	Recording	Sampling frequency
PA3000	2020/12/31	100ms values	10kHz

Results are presented in the following table and graphs:

	Ramp range desired	Time Setting (s)	Time Measured (s)	Final Value (Hz)	Ramp (Hz/s)	Disconnection
Positive frequency drift	50.0 Hz	0	--	--	--	<input checked="" type="checkbox"/> NO <input type="checkbox"/> YES
	50.0Hz to 51.0Hz	0.5	0.5	50.98	1.960	<input checked="" type="checkbox"/> NO <input type="checkbox"/> YES
	50.0Hz to 51.0Hz	0.5	0.5	50.96	1.920	<input checked="" type="checkbox"/> NO <input type="checkbox"/> YES
	51.5Hz	1.0	0.9	51.50	0.000	<input checked="" type="checkbox"/> NO <input type="checkbox"/> YES
	51.0Hz to 51.5Hz	0.5	0.6	51.50	0.833	<input checked="" type="checkbox"/> NO <input type="checkbox"/> YES
Negative frequency drift	50.0 Hz	0	--	50	--	<input checked="" type="checkbox"/> NO <input type="checkbox"/> YES
	50.0Hz to 49.0Hz	0.5	0.6	48.95	-1.750	<input checked="" type="checkbox"/> NO <input type="checkbox"/> YES
	49.0Hz to 47.5Hz	0.5	0.6	49.01	-1.650	<input checked="" type="checkbox"/> NO <input type="checkbox"/> YES
	47.5 Hz	1.0	0.9	47.50	0.000	<input checked="" type="checkbox"/> NO <input type="checkbox"/> YES
	47.5Hz to 49.0Hz	1.5	1.5	47.50	-1.007	<input checked="" type="checkbox"/> NO <input type="checkbox"/> YES





4.5.2 Voltage ride through (UVRT/OVRT)

These tests have been required according to chapters D.5.2 and D.5.3 of the standard. The aim is to determine whether the EUT is capable of detecting a grid fault and riding through it without disconnecting.


It is not applicable due to the EUT is type A in accordance with NC RfG, which is not going to connection to the plant above 1MW.

4.6 ACTIVE RESPONSE TO FREQUENCY DEVIATIONS

4.6.1 Power response to overfrequency

This test has been done according to chapter D.6.1 of the standard in order to verify the capability of the EUT of activating power response to overfrequency.

For this automatic response function, an initial delay of less than 2 seconds, between the intentional and the intrinsic delay, shall be configured. This function shall activate once frequency rises over a frequency threshold configurable between 50.2-52.0 Hz. Once activated, this function shall be capable of reducing active power with a configurable droop in a range of 2-12%.



For every step of power decrease (grid frequency increase), an active power rise time of maximum 10s is to be observed for 50 % Pmax. Maximum settling time shall be a maximum of 30 s.

For every step of power increase (grid frequency decrease), an active power rise time of maximum 2s is to be observed for 50 % Pmax. Maximum settling time shall be a maximum of 20 s.

In order to verify this function, the parameter setting as following to perform the test:

- Test 1: P = 100 %Pn ; f1 = 50.2 Hz; droop = 12 %; f-stop deactivated, with delay of 2 s (*)
- Test 2: P = 100 %Pn; f1 = 52 Hz; droop = 2 %; f-stop deactivated, no delay
- Test 3: P = 50 %Pn; f1 = 51 Hz; droop = 5 %; f-stop deactivated, no delay

(*) The intentional delay is only active for the activation of the function, once the function is operating, the established control loop is not intentionally delayed.


Note: Threshold for disconnection overfrequency protection is set at 52.0 Hz at each test items.

Used settings of the measurement device for this measurement:

Measurement device	Date of measurement	Recording	Sampling frequency
PA3000	2021/2/18	100ms values	10kHz


Test results are offered at the table below:

Test 1							
Step	f (Hz)	P desired (%Pn)	Frequency meas. (Hz)	P meas. (%Pn)	P deviation (%Pn) (Within ± 10 %)	Step response time Tsr(s)	Settling time Ts(s)
1	50.00 ± 0.05 Hz	100.0	50.00	100.1	0.1	--	--
2	50.20 ± 0.05 Hz	100.0	50.20	100.2	0.2	0.1	0.1
3	51.00 ± 0.05 Hz	86.7	51.00	86.9	0.2	2.2	2.2
4	51.80 ± 0.05 Hz	73.3	51.80	73.6	0.3	0.4	0.4
5	50.20 ± 0.05 Hz	100.0	50.20	100.3	0.3	0.4	0.4
6	50.00 ± 0.05 Hz	100.0	50.00	100.3	0.3	0.2	0.2




Test 2							
Step	f (Hz)	P desired (%Pn)	Frequency meas. (Hz)	P meas. (%Pn)	P deviation (%Pn) (Within ± 10 %)	Step response time Tsr(s)	Settling time Ts(s)
1	50.00 ± 0.05 Hz	100.0	50.00	100.4	0.4	--	--
2	50.50 ± 0.05 Hz	100.0	50.50	100.4	0.4	--	--
3	51.00 ± 0.05 Hz	100.0	51.00	100.4	0.4	0.2	0.2
4	51.50 ± 0.05 Hz	100.0	51.50	100.5	0.5	0.2	0.2
5	51.80 ± 0.05 Hz	100.0	51.80	100.4	0.4	0.1	0.1
6	52.20 ± 0.05 Hz	0.0	52.20	0.0	0.0	0.2	0.2

P vs f chart for Test 2




Test 3							
Step	f (Hz)	P desired (%Pn)	Frequency meas. (Hz)	P meas. (%Pn)	P deviation (%Pn) (Within ± 10 %)	Step response time Tsr(s)	Settling time Ts(s)
1	50.00 ± 0.05 Hz	50.0	50.00	50.4	0.4	--	--
2	51.00 ± 0.05 Hz	50.0	51.00	50.4	0.4	0.2	0.2
3	51.20 ± 0.05 Hz	46.0	51.20	46.5	0.5	0.2	0.2
4	51.70 ± 0.05 Hz	36.0	51.70	36.5	0.5	0.4	0.4
5	51.30 ± 0.05 Hz	44.0	51.30	44.5	0.5	0.2	0.2
6	51.00 ± 0.05 Hz	50.0	51.00	50.4	0.4	0.3	0.3
7	50.00 ± 0.05 Hz	50.0	50.00	50.4	0.4	0.2	0.2



4.6.2 Power response to underfrequency

This test has been done according to chapter D.6.2 of the standard in order to verify the capability of the EUT of activating power response to underfrequency.

For this automatic response function, an initial delay of less than 2 seconds, between the intentional and the intrinsic delay, shall be configured. This function shall activate once frequency rises over a frequency threshold configurable between 49.8-46.0 Hz. Once activated, this function shall be capable of reducing active power with a configurable droop in a range of 2-12%.



For every step of power decrease (grid frequency increase), an active power rise time of maximum 10s is to be observed. Maximum settling time shall be a maximum of 30 s.

For every step of power increase (grid frequency decrease), an active power rise time of maximum 2s is to be observed. Maximum settling time shall be a maximum of 20 s.

In order to verify this function, the parameter setting as following to perform the test:

- Test 1: $P_M = -20 \%P_n$; $f_1 = 49.8 \text{ Hz}$; droop = 12 %; f-stop deactivated, with delay of 2 s (*)
- Test 2: $P_M = -20 \%P_n$; $f_1 = 48 \text{ Hz}$; droop = 2 %; f-stop deactivated, no delay
- Test 3: $P_M = 50 \%P_n$; $f_1 = 49.8 \text{ Hz}$; droop = 5 %; f-stop deactivated, no delay

(*) The intentional delay is only active for the activation of the function, once the function is operating, the established control loop is not intentionally delayed.

Note 1: Active power in negative value means that the unit is working in charging operation method. While when active power values are given in positive value, this means that the unit is working discharge operation mode.

Note 2: Threshold for disconnection underfrequency protection is set at 45.8Hz at each test items.


Used settings of the measurement device for this measurement:

Measurement device	Date of measurement	Recording	Sampling frequency
PA3000	2021/1/5	100ms values	10kHz

Test results are offered at the table below:


Test 1							
Step	f (Hz)	P desired (%Pn)	Frequency meas. (Hz)	P meas. (%Pn)	P deviation (%Pn) (Within ± 10 %)	Step response time Tsr(s)	Settling time Ts(s)
1	50.00 ± 0.05 Hz	-20.0	50.00	-19.9	0.1	--	--
2	49.80 ± 0.05 Hz	-20.0	49.80	-19.9	0.1	0.2	0.2
3	49.50 ± 0.05 Hz	-15.0	49.50	-14.9	0.1	0.4	0.4
4	48.00 ± 0.05 Hz	10.0	48.00	10.8	0.8	0.7	0.7
5	46.00 ± 0.05 Hz	43.3	46.00	44.2	0.9	0.8	0.8
6	47.50 ± 0.05 Hz	18.3	47.50	19.0	0.7	0.7	0.7
7	49.80 ± 0.05 Hz	-20.0	49.80	-19.6	0.4	0.6	0.8
8	50.00 ± 0.05 Hz	-20.0	50.00	-19.6	0.4	0.2	0.2

Note: Active power in negative value means that the unit is working in charging operation method. While when active power values are give in positive value, this menas that the unit is working discharge operation mode.




Test 2							
Step	f (Hz)	P desired (%Pn)	Frequency meas. (Hz)	P meas. (%Pn)	P deviation (%Pn) (Within $\pm 10\%$)	Step response time Tsr(s)	Settling time Ts(s)
1	50.00 \pm 0.05 Hz	-20	50.00	-20.7	-0.7	--	--
2	49.80 \pm 0.05 Hz	-20	49.79	-20.7	-0.7	0.2	0.2
3	49.50 \pm 0.05 Hz	-20	49.50	-20.7	-0.7	0.1	0.1
4	48.00 \pm 0.05 Hz	-20	48.01	-20.7	-0.7	0.2	0.2
5	46.00 \pm 0.05 Hz	100	46.00	100.1	0.1	0.3	0.3
6	47.50 \pm 0.05 Hz	30	47.50	31.8	1.8	1.8	1.8
7	49.80 \pm 0.05 Hz	-20	49.80	-20.7	-0.7	2.1	2.1
8	50.00 \pm 0.05 Hz	-20	50.00	-20.7	-0.7	0.2	0.2

Note: Active power in negative value means that the unit is working in charging operation method. While when active power values are given in positive value, this means that the unit is working discharge operation mode.



Test 3							
Step	f (Hz)	P desired (%Pn)	Frequency meas. (Hz)	P meas. (%Pn)	P deviation (%Pn) (Within ± 10 %)	Step response time Tsr(s)	Settling time Ts(s)
1	50.00 ± 0.05 Hz	50	50.00	50.3	0.3	--	--
2	49.80 ± 0.05 Hz	50	49.80	50.3	0.3	0.2	0.2
3	49.50 ± 0.05 Hz	62	49.50	62.7	0.7	0.5	0.5
4	48.00 ± 0.05 Hz	100	48.00	100.4	0.4	3.0	3.0
5	46.00 ± 0.05 Hz	100	46.00	99.8	-0.2	0.2	0.2
6	47.50 ± 0.05 Hz	100	47.50	100.5	0.5	0.1	0.1
7	49.80 ± 0.05 Hz	50	49.80	50.4	0.4	0.9	0.9
8	50.00 ± 0.05 Hz	100	50.00	100.3	0.3	0.8	0.8

Note: Active power in negative value means that the unit is working in charging operation method. While when active power values are given in positive value, this means that the unit is working discharge operation mode.




4.7 POWER RESPONSE TO VOLTAGE CHANGES

The aim of this test is to evaluate the reactive power capability of the EUT both at registered capacity and below registered capacity


4.7.1 Q(P) Capabilities

These tests have been done according to chapter D.7.1 of the standard. The aim is to verify compliance with the following characteristic included in the standard at rated voltage:

For LV connections:



For HV connections:



Note: for HV connections default requirements of the curve above shall be considered.

Just operating conditions as requested by the customer LV shall be verified.

The compliances with the requirements of clause D.6.1 of the standard is stated in section 4.4.1 of following test report:

Additionally, the following result is recalculated with P_D is 5.4kW



Used settings of the measurement device for this measurement:

Measurement device	Date of measurement	Recording	Sampling frequency
PA3000	2020/12/31, 2021/1/4, 2020/1/18	100ms values	10kHz

4.7.1.1 Fixed Power Factor (PF = 1)

This test has been done configuring a reactive power setpoint of 0 kVAr, therefore obtaining a power factor of 1. Steps measured and results are included in the following table and graph:

Fixed Power Factor (PF=1)						
P Desired (%P _D)	Power DC (kW)	P measured (%P _D)	Q measured (%P _D)	Power Factor desired (cos φ)	Power Factor measured (cos φ)	Power Factor Deviation (cos φ)
0	0.102	2.2	2.3	--	0.481	--
6	0.203	6.0	2.3	--	0.860	--
11	0.358	11.6	2.3	--	0.955	--
17	0.509	17.3	2.3	1	0.993	-0.007
22	0.687	23.5	2.3	1	0.993	-0.007
28	0.836	28.6	2.7	1	0.993	-0.007
33	0.978	33.8	2.7	1	0.994	-0.006
39	1.133	39.3	2.9	1	0.995	-0.005
44	1.291	44.8	2.9	1	0.996	-0.004
50	1.449	50.4	2.9	1	0.997	-0.003
56	1.607	55.9	2.9	1	0.997	-0.003
61	1.768	61.4	3.2	1	0.998	-0.002
67	1.928	67.0	3.2	1	0.998	-0.002
72	2.089	72.6	3.2	1	0.998	-0.002
78	2.249	78.1	3.2	1	0.998	-0.002
83	2.411	83.6	3.2	1	0.998	-0.002
89	2.576	89.2	3.2	1	0.999	-0.001
94	2.740	94.8	3.2	1	0.999	-0.001
100	2.906	100.3	3.2	1	0.999	-0.001
106	3.072	105.9	3.2	1	0.999	-0.001
111	3.240	111.5	3.2	1	0.999	-0.001



4.7.1.2 Rectangular curve – Fixed reactive power

This requirement has been done for the verification of the rectangular curve at a fixed reactive power level at both the inductive and the capacitive side.

t is not applicable due to the EUT is not going to connect to HV grid.

4.7.1.3 Triangular curve – Fixed power factor (PF = 0.9)


This test has been done for verification of the triangular curve, at both the inductive and the capacitive side:

Triangular Curve (PF=0.9 / capacitive)						
P Desired (%P _D)	Power DC (kW)	P measured (%P _D)	Q measured (%P _D)	Power Factor desired (cos φ)	Power Factor measured (cos φ)	Power Factor Deviation (cos φ)
0	0.1	3.5	4.0	--	0.474	--
7	0.2	7.4	-3.7	--	0.850	--
13	0.4	13.1	-5.8	--	0.894	--
19	0.5	18.9	-8.1	0.9	0.903	0.003
25	0.7	24.8	-11.0	0.9	0.901	0.001
31	0.8	30.6	-13.4	0.9	0.904	0.004
36	1.0	36.4	-16.8	0.9	0.895	-0.005
42	1.1	42.2	-19.5	0.9	0.897	-0.003
48	1.3	48.1	-22.1	0.9	0.897	-0.003
54	1.5	54.0	-24.7	0.9	0.898	-0.002
60	1.6	59.9	-27.4	0.9	0.899	-0.001
66	1.8	65.9	-30.1	0.9	0.899	-0.001
72	1.9	71.8	-32.7	0.9	0.899	-0.001
78	2.1	77.8	-35.3	0.9	0.899	-0.001
84	2.3	83.8	-38.0	0.9	0.900	0.000
90	2.4	89.9	-40.7	0.9	0.900	0.000
96	2.6	96.0	-43.4	0.9	0.900	0.000
102	2.8	102.2	-46.1	0.9	0.900	0.000
108	2.9	108.4	-48.8	0.9	0.900	0.000
111(*)	2.9	108.7	-48.9	0.9	0.900	0.000


(*) The inverter does not reach the fixed power factor value of 0.9 due to the current limitation function.

Triangular Curve (PF=0.9 / inductive)						
P Desired (%P _D)	Power DC (kW)	P measured (%P _D)	Q measured (%P _D)	Power Factor desired (cos φ)	Power Factor measured (cos φ)	Power Factor Deviation (cos φ)
0	0.1	3.6	4.3	--	0.483	--
7	0.2	7.3	4.2	--	0.819	--
13	0.4	13.1	5.7	--	0.898	--
19	0.5	18.8	8.4	0.9	0.898	-0.002
25	0.7	24.6	10.7	0.9	0.905	0.005
31	0.8	30.4	13.8	0.9	0.898	-0.002
36	1.0	36.1	16.4	0.9	0.899	-0.001
42	1.1	41.9	18.9	0.9	0.900	0.000
48	1.3	47.8	21.5	0.9	0.901	0.001
54	1.4	53.7	24.1	0.9	0.902	0.002
60	1.6	59.6	26.8	0.9	0.902	0.002
66	1.8	65.5	29.4	0.9	0.902	0.002
72	1.9	71.5	32.0	0.9	0.902	0.002
78	2.1	77.4	34.6	0.9	0.902	0.002
84	2.3	83.4	37.3	0.9	0.902	0.002
90	2.4	89.2	39.8	0.9	0.902	0.002
96	2.6	95.3	42.4	0.9	0.902	0.002
102	2.7	101.3	45.1	0.9	0.902	0.002
108	2.9	107.5	47.7	0.9	0.902	0.002
111	3.0	111.6	49.5	0.9	0.902	0.002


Triangular Curve (PF=0.9), Inductive: Power factor and powers vs Time



Triangular Curve (PF=0.9), Capacitive side: Power Factor and Powers vs Time



Triangular Curve: Active power vs Reactive power



4.7.1.4 Semicircular curve – Maximum apparent power


This requirement is for verification of the semicircular characteristic at rated voltage at both the inductive and the capacitive side.

It is not test due to it is optional.

4.7.2 Q(U) capabilities

This test has been done according to chapter D.7.1 of the standard. The aim is to verify the reactive power capabilities of the EUT at different voltage levels than the rated level. For verification of this requirement, the following characteristic from the standard shall be tested:

For LV connections:



The max. Q setting as following table with is stricter than the standard. Only the condition for connection to LV grid had been verified as following,



Used settings of the measurement device for this measurement:

Measurement device	Date of measurement	Recording	Sampling frequency
PA3000	2021/01/04	100ms values	10kHz

Test results are presented in the following table and graph:

Reactive power capability at active power PD in the voltage range							
Step	Voltage desired (p.u.)	Voltage Meas. (p.u.)	P measured (%PD)	Q measured (%PD)	Q desired (%PD)	Q deviation (%PD)	Power Factor measured (cos φ)
1	1.100	1.101	97.9	-53.9	-53.8	-0.1	0.876
2	1.100	1.101	111.7	5.3	0.0	5.3	0.999
3	1.050	1.050	101.7	54.3	53.8	0.5	0.882
4	1.000	1.001	101.7	53.9	53.8	0.1	0.884
5	0.900	0.900	92.6	53.3	53.8	-0.5	0.867
6	0.850	0.851	86.5	52.5	53.8	-1.3	0.855
7	0.850	0.851	99.8	-4.7	0.0	-4.7	0.999
8	0.900	0.901	105.4	-4.7	0.0	-4.7	0.999
9	0.950	0.950	95.2	-54.8	-53.8	-1.0	0.867
10	1.000	1.000	97.9	-54.5	-53.8	-0.7	0.874

Q(U) capabilities



4.7.3 Cos φ setpoint

This test has been done according to chapter D.7.1 of the standard.

The dynamic accuracy shall be in accordance with Figure 15 of EN50549-1:2019 in the standard with a maximum tolerance of $\pm 5\%$ of P_D plus a time delay of up to 3 seconds deviating from an ideal first order filter response.





Figure 15 — Example of dynamic control response and tolerance band for a step from $Q=0$ to $Q=33\%P_D$ with $\tau=3,33s$

Used settings of the measurement device for this measurement:

Measurement device	Date of measurement	Recording	Sampling frequency
PA3000	2021/1/4,	100ms values	10kHz

Test results are offered at the tables below.

%Pn	Steps	Time measured (s)
50	Q = 0 → Q = 33 %Sn	t = 1.6
	Q = 33 %Sn → Q = 33 %Sn	t = 3.0
	Q = 33 %Sn → Q = 0	t = 1.2




4.7.4 Cos φ (P) capabilities

This test has been done according to chapter D.7.1 of the standard.

The compliances with the requirements of clause D.7.1 of the standard is stated in section 4.4.2.4 of EN 50549-1:2019.

The power related control mode cos φ (P) controls the cos φ of the output as a function of the active power output.

For power related control modes, a characteristic defined by the manufacturer as following:



Resulting from a change in active power output a new cos φ set point is defined according to the set characteristic. The response to a new cos φ set value shall be as fast as technically feasible to allow the change in reactive power to be in synchrony with the change in active power. The new reactive power set value shall be reached at the latest within 10 s after the end value of the active power is reached. The static accuracy of each cos φ set point shall be according to 4.7.2.2 of EN 50549-1:2019.

Used settings of the measurement device for this measurement:


Measurement device	Date of measurement	Recording	Sampling frequency
PA3000	2021/1/4	100ms values	10kHz

The results are offered in the table below (Note: 10 %P_n have not measured in following test):


Setting cos φ (P) with the standard characteristic curve (20%P _n to 100%P _n)						
Active power setting (%P _{Emax})	Active power measured (p.u.)	Reactive power measured (p.u.)	cos φ measured	Desired cos φ	Δ cos φ (< 0.01)	Transient period (< 10 s)
20	0.205	-0.021	0.992	1	-0.008	1.5
30	0.295	-0.014	0.994	1	-0.006	1.5
40	0.400	0.003	0.996	1	-0.004	5.1
50	0.493	-0.016	0.996	1	-0.004	5.6
60	0.592	-0.125	0.979	0.98	-0.001	6.3
70	0.695	-0.207	0.959	0.96	-0.001	5.7
80	0.796	-0.291	0.939	0.94	-0.001	5.6
90	0.892	-0.379	0.920	0.92	0.000	4.7
100 (*)	0.919	-0.418	0.909	0.90	0.009	7.4

(*) Because of limited by apparent power, the active does not reach to 100 % when cos φ = 0.9

Setting $\cos \phi(P)$ with standard characteristic curve (20 %Pn to 100 %Pn)



Power factor vs Active Power



4.7.5 Specific for a small power-generating plant

This test has been done according to chapter D.7.1.1 of the standard.

- When the voltage $\leq 105\%$ U_n : $\cos \phi = 1$ ($Q=0$)
- When the voltage $> 105\%$ U_n : free operation with $1 \geq \cos \phi > 0,9$ under-excited. (no over-excited operation allowed)


Used settings of the measurement device for this measurement:

Measurement device	Date of measurement	Recording	Sampling frequency
PA3000	2021/1/18	100ms values	10kHz

The compliances with the requirements of clause D.7.1.1 of the standard is stated in section 4.4.2.4 of following test report:

PF vs Voltage						
P setpoint (%P _n)	Voltage setpoint	V measured (p.u.)	P measured (p.u.)	cos ϕ measured	Desired cos ϕ	Δ cos ϕ (< 0.01)
20	1.060	1.061	0.212	0.994	1.000	0.006
30	1.060	1.059	0.305	0.993	1.000	0.007
40	1.060	1.059	0.405	0.996	1.000	0.004
50	1.060	1.059	0.505	0.989	1.000	0.011
60	1.060	1.059	0.588	0.980	0.980	0.000
70	1.060	1.060	0.688	0.961	0.960	-0.001
80	1.060	1.060	0.792	0.941	0.940	-0.001
90	1.060	1.060	0.892	0.922	0.920	-0.002
100(*)	1.060	1.060	0.903	0.913	0.900	-0.013
100	1.040	1.040	0.996	0.999	1.000	0.001
90	1.040	1.040	0.905	0.999	1.000	0.001
80	1.040	1.041	0.805	0.999	1.000	0.001
70	1.040	1.041	0.705	0.998	1.000	0.002
60	1.040	1.041	0.605	0.998	1.000	0.002
50	1.040	1.041	0.505	0.997	1.000	0.003
40	1.040	1.041	0.406	0.996	1.000	0.004
30	1.040	1.040	0.305	0.994	1.000	0.006
20	1.040	1.040	0.212	0.994	1.000	0.006

(*) The inverter does not reach 100%P_n due to the current limitation function.



4.7.6 Specific for another (not small) power-generating plant


This test has been required according to chapter D.7.1.2 of the standard.

It is not applicable due to the EUT is type A in accordance with NC RfG, which is not goint to connection to the plant above 1MW.

4.7.7 Voltage related active power reduction P(U)

This test has been done according to chapter D.7.2 of the standard. The aim is to verify that the EUT is capable of reducing active power in overvoltage situations to avoid disconnection without causing

The following parameters have been set by the manufacturer for this test:



Test 1 and Test 2 setpoint as following:


Reference	Test 1 Set points		Test 2 Set points	
	Volt. (%Un)	Power (%Pn)	Volt. (%Un)	Power (%Pn)
V1	90.0%	100%	90.0%	100%
V2	95.6%	100%	95.6%	100%
V3	104.0%	100%	108.7%	100%
V4	110.0%	20%	115.2%	20%


Used settings of the measurement device for this measurement:

Measurement device	Date of measurement	Recording	Sampling frequency
PA3000	2021/1/4	100ms values	10kHz

Test results are offered at tables below.

Volt-Watt TEST 1				
V setting (p.u.)	V meas. (p.u.)	P desired (p.u.)	P meas. (p.u.)	P deviation (p.u.)
0.900	0.901	1.000	0.951	-0.049
0.950	0.950	1.000	1.001	0.001
1.000	1.000	1.000	1.021	0.021
1.020	1.021	1.000	1.021	0.021
1.040	1.040	1.000	1.022	0.022
1.050	1.053	0.886	0.895	0.009
1.060	1.059	0.771	0.771	0.000
1.070	1.070	0.657	0.647	-0.010
1.100	1.101	0.200	0.186	-0.014
Volt-Watt TEST 2				
V setting (p.u.)	V meas. (p.u.)	P desired (p.u.)	P meas. (p.u.)	P deviation (p.u.)
0.900	0.901	1.000	0.951	-0.049
0.950	0.950	1.000	1.001	0.001
1.000	1.000	1.000	1.016	0.016
1.020	1.021	1.000	1.016	0.016
1.040	1.040	1.000	1.017	0.017
1.050	1.050	1.000	1.017	0.017
1.060	1.060	1.000	1.017	0.017
1.070	1.070	1.000	1.018	0.018
1.100	1.101	0.840	0.838	-0.002
1.120	1.120	0.584	0.588	0.004
1.152	1.152	0.200	0.186	-0.014





4.7.8 Provision of additional fast reactive current during faults and voltage steps

This test has been done according to chapter D.7.3 of the standard.

It is not applicable due to the EUT is type A in accordance with NC RfG, which is not going to connection to the plant above 1MW.

4.8 CONNECTION AND STARTING TO GENERATE ELECTRICAL POWER

4.8.1 Automatic reconnection after tripping

This test has been done according to chapter D.8 of the standard. The aim of the test is to verify that the EUT reconnects after tripping if set conditions are met. This function shall have configurable thresholds for both voltage and frequency as well as configurable observation time and recuperation gradient. After a disconnection due to a fault, the EUT is allowed to reconnect when frequency and voltage values have been within the thresholds for at least the observation time configured. When reconnecting, this shall occur with the ramp rate established.

The following table include default values presented in the standard:

Just operating conditions as requested by the customer LV shall be verified.

Parameter	Reconnection after tripping of the interface protection relay	Normal operation starting
Lower frequency	49,9 Hz	49,9 Hz
Upper frequency	50,1 Hz	50,1 Hz
Lower voltage	If connection to the LV distribution network: 85% U_n	If connection to the LV distribution network: 85% U_n
	If connection to the HV distribution network: 90 % U_c	If connection to the HV distribution network: 90 % U_c
Upper voltage	If connection to the LV distribution network: 110 % U_n	If connection to the LV distribution network: 110 % U_n
	If connection to the HV distribution network: 110 % U_c	If connection to the HV distribution network: 110 % U_c
Observation time	60 s	60 s
Maximum active power increase gradient	10 %/min*	20 %/min
* Power-generating units that have not the ability to apply a certain gradient shall take into account an additional delay.		

Used settings of the measurement device for this measurement:

Measurement device	Date of measurement	Recording	Sampling frequency
PA3000	2021/1/4	100ms values	10kHz

Test results are presented in the following table and graphs:

Operation mode	Observation time measured (s)	Gradient measured (%Pn/min)
Overvoltage	67.6	7.89
Undervoltage	71.0	7.88
Overfrequency	70.7	7.84
Underfrequency	70.7	7.84

Note: the test graph see in section 4.8.2 of this report.

4.8.2 Starting to generate electrical power

This test has been done according to chapter D.8 of the standard. The aim of the test is to verify that the EUT starts to generate power within previously configured conditions. This function shall have configurable thresholds for both voltage and frequency as well as configurable observation time and recuperation gradient. Once the EUT is connected, when frequency and voltage values get within the thresholds for at least the observation time configured, it shall start to generate power with the configured ramp rate.

The following table include default values presented in the standard:

Just operating conditions as requested by the customer LV shall be verified.

Parameter	Reconnection after tripping of the interface protection relay	Normal operation starting
Lower frequency	49,9 Hz	49,9 Hz
Upper frequency	50,1 Hz	50,1 Hz
Lower voltage	If connection to the LV distribution network: 85% U_n	If connection to the LV distribution network: 85% U_n
	If connection to the HV distribution network: 90 % U_c	If connection to the HV distribution network: 90 % U_c
Upper voltage	If connection to the LV distribution network: 110 % U_n	If connection to the LV distribution network: 110 % U_n
	If connection to the HV distribution network: 110 % U_c	If connection to the HV distribution network: 110 % U_c
Observation time	60 s	60 s
Maximum active power increase gradient	10 %/min*	20 %/min
* Power-generating units that have not the ability to apply a certain gradient shall take into account an additional delay.		

Used settings of the measurement device for this measurement:


Measurement device	Date of measurement	Recording	Sampling frequency
PA3000	2021/1/4	100ms values	10kHz

Test results are presented in the following table and graphs:


Operation mode	Observation time measured (s)	Gradient measured (%Pn/min)
Overvoltage	69.9	8.41
Undervoltage	71.5	7.77
Overfrequency	71.6	7.86
Underfrequency	71.4	7.83



Test results are presented in the following graphs for connection and reconnection

Overvoltage Connection and Reconnection



Undervoltage Connection and Reconnection





4.9 CEASING AND REDUCTION OF ACTIVE POWER ON SET POINT


4.9.1 Ceasing active power

The test has been required according to the clause D.9.1 of the standard.

Generating plants with a maximum capacity of 0.8 kW or more shall be equipped with a logic interface (input port) in order to cease active power output within 5 seconds following an instruction being received at the input port. If required by the DSO and the responsible party, this includes remote operation.

Used settings of the measurement device for this measurement:

Measurement device	Date of measurement	Recording	Sampling frequency
DS05014A	2021/1/5	--	100kHz



4.9.2 Active power reduction following setpoint

This test has been done according to chapter D.9.2 of the standard. The aim is to verify the capacity of the EUT of reducing active power following an instruction at the input port.

It is not test due to it is not mandatory for connections of <1MW, and the inverter is tested only according to requirements for Type A plant generation.

4.10 COMMUNICATION – REMOTE MONITORING AND CONTROL

The requirements of this Section are applicable only to the power-generating units that are part of:

- a power-generating module with a maximum power ≥ 1 MW
- a power-generating plant with a maximum power > 250 kVA, if so required by the DSO, respecting the regional regulatory provisions.

The power-generating unit must have the necessary functionalities to meet the requirements of the section 7.13 of the standard concerning the communication (remote control and monitoring).

- Communication signals of the power-generating module to the DSO

Information	Nature	Max refresh time	Comment
Voltages at the point of connection	Measurement	1 s	
Active power at the point of connection	Measurement	1 s	
Reactive power at the point of connection	Measurement	1 s	
Active power on the terminals of the power-generating module	Measurement	1 s	Only required if at least one of the following conditions has been met: <ul style="list-style-type: none"> • $\frac{\text{local consumption power of the DSU}}{P_n \text{ of the power-generating module}} > 30 \%$ • Local consumption power of the DSU > 300 kVA
Reactive power on the terminals of the power-generating module	Measurement	1 s	Only required if at least one of the following conditions has been met: <ul style="list-style-type: none"> • $\frac{\text{local consumption power of the DSU}}{P_n \text{ of the power-generating module}} > 30 \%$ • Local consumption power of the DSU > 300 kVA
Unavailability of the communication system		1 s	Can be specific to the protocol used
Power-generating plant connected to the distribution network	Binary signal	1 s	For every disconnection breaker and backup disconnection breaker a signal must be given that indicates the status (open/closed) of the breaker.
Watchdog on RTU auxiliary energy source			

- Communication signals from DSO to power-generating module

Operation parameter	Type of signal	Max. operation time ²²	Comment
Request for disconnect	Binary signal	1 s	1 = Request for disconnection 0 = End of request for disconnection
Limit for the request to limit the produced active power	Value	1 s	Value from 0 to 100 % of P _n
Value of fixed setpoint for reactive power	Value	1 s	-100 %..., 100 % of P _n
Selection of the reactive power control modus		1 s	No control (free use of reactive power capabilities by DSU) Q setpoint Q(U) Q(P) Cosφ setpoint Cosφ(P)


It is not evidenced due to power-generating units is not one of above.

5 PICTURES

Front




Back Side



C10/11: 2019

Internal View



Software Version and Serial Number of the EUT

```
System Information(1)
Product SN:           ZE1ES050M31999
Software Version:    V2.80
Hardware Version:    V1.00
RS485 Address:      01
```

6 ELECTRICAL SCHEMES

